

State of Kansas



WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JOHN C. WOELK Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Dear Sir:

Mr. Dick Defenbach of Rains & Williamson Oil Co has this date requested permission to plug the following described well:

Mr. Defenbach guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc., and Rains & Williamson Oil Co.

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Messenger Well No. # 1

Location: C SW SW Sec. 8 Twp. 30 Rge. 6 (E)(W) W

County Kingman Total Depth 4556' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Defenbach was instructed to plug the well as follows:

300' of 8 5/8" surface pipe, cement circulated with 275 sacks.

Fill hole with drilling mud to 280', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving  
 Conservation Division Agent

