

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. B. Y. Newman of J. E. Newman has this

date requested permission to plug the following described well:

Mr. Newman guarantees payment of the plugging fee.

Operator's full Name: J. E. Newman

Complete Address: 2005 Tower Bldg., Denver, Colorado

Lease Name: Earlywine Well No. # 1

Location: SE SE NE Sec. 15 Twp. 27 Rge. 15 (E) (W) W

County Pratt Total Depth 4600 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Newman was instructed to plug the well as follows:

320' of 8 5/8" surface pipe, cement circulated with 300
sacks. 4552' of 4 1/2" long string, cemented with 200 sacks.
Plugged back to 4500'. Perforation 4432' to 39'. Sand
to 4410', cement with 3 sacks. Fill hole with mud to
240', 10' rock bridge, cement with 20 sacks. Fill hole
to 40', 10' rock bridge, cement with 10 sacks to base cellar.
 Very truly yours,

Archie Elving
 Conservation Division Agent