



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 18 1964

03-18-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Co.

Complete Address: Box 267, Great Bend, Kansas

Lease Name: J. Becker Well No. # 1

Location: SE NW SE Sec. 5 Twp. 28 Rge. 12 (E) (W) W

County Pratt Total Depth 4511 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

257' of 13 3/8" surface pipe, cemented with 250 sacks. Fill hole with drilling mud to 250'; 1st cementing plug, bridge with hulls, and cement with 40 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 20 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent