

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

OCT 24 1972

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sweetman of Sweetman Drlg. Co. has this
date requested permission to plug the following described well:Mr. Sweetman guarantees payment of the plugging fee.Operator's full Name: Halliburton Oil Producing Co.Complete Address: 117 Cameron Bldg Oklahoma City, OKLease Name: Barker Well No. 1Location: SW/SW/NE Sec. 3 Twp. 28s Rge. 12 (E)(W) WCounty: Pratt Total Depth 4470 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Sweetman was instructed to plug the well as follows:328 ft 10 3/4 surface pipe cemented with 300 sacks. Pump50 sacks cement to 300 ft. Mud to 40 ft, plug, 1/2 sackhulls, 15 sacks cement to surface. 2 sacks cement in
rat hole.Pumped by Halliburton Cementing Co. Great Bend, Ks

Very truly yours,

Conservation Division Agent