

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

STAMPED  
 51416 01.10.1963

JAN 29 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Ralph Glen of Glen & Smith Pulling Co. has this  
 date requested permission to plug the following described well:

Mr. Ralph Glen guarantees payment of the plugging fee.

Operator's full Name: Santa Fe Pipe and Supply

Complete Address: Box 562, Great Bend, Kansas

Lease Name: Rose Well No. # 1

Location: NW NW NE Sec. 27 Twp. 28 Rge. 11 (E) (W) W

County Pratt Total Depth 4601 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Glen was instructed to plug the well as follows:

310' of 8 5/8" surface pipe circulated with cement. 4554'  
5 1/2" long string cemented with 125 sacks. Plugged back to  
4370'. Top of Perforation 4337', sanded to 4330' cemented  
with 5 sacks. Fill hole to 200' and 10' rock bridge cement-  
ed with 20 sacks. Fill hole with mud to 40' and 10' rock  
bridge with 10 sacks cement to base cellar.

Very truly yours,

Arlene Elving  
 Conservation Division Agent