

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CORPORATION COMMISSION
OCT 27 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed October 5, 1967.

Dear Sir:

Mr. Gerd Steincamp of Strata Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Roger Williams Oil Company

Complete Address: 11 1/2 East Main, Chanute, Kansas 66720

Lease Name: Dudrey Well No. # 1

Location: SW NE SW Sec. 34 Twp. 28 Rge. 11 (E) (W) W

County Pratt Total Depth 4540' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

330' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill
hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sacks of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat & mouse holes with 4 sack

Very truly yours,

Audie Elving
Conservation Division Agent