

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21379-00-00
Spot: SWNWNWSE Sec/Twnshp/Rge: 19-14S-32W
2080 feet from S Section Line, 2440 feet from E Section Line
Lease Name: MCGUIRE B Well #: 1
County: LOGAN Total Vertical Depth: 4408 feet

Operator License No.: 34639
Op Name: BLACK TEA OIL, LLC
Address: 1014 E. 29TH ST.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4406		240 SX
SURF	8.625	265		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2015 9:00 AM
Plug Co. License No.: 34821 Plug Co. Name: K & M WELL SERVICE INC.
Proposal Rcvd. from: COLE DINKEL Company: K & M WELL SERVICE INC. Phone: (785) 445-2441

Proposed Plugging Method: Ordered 475 sx 60/40 pozmix 4% gel cement w/500 # hulls and 16 sx gel.
Shot perforations at 2100', 1030' and 260'.
Perforations: 4436' - 4342', 4324' - 4332' and 4288' - 4294'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2015 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4310' and pumped 16 sx gel followed by 65 sx cement w/250 # hulls. Pulled tubing to 2134' and pumped 300 sx cement with good circulation of cement out of the casing and the backside. Pulled tubing out and topped off w/50 sx cement full.
GPS: 38.82040 -100.91830

Perfs:

Top	Bot	Thru	Comments
4336	4342		
4324	4332		
4288	4294		

Remarks: GLOBAL CEMENT TICKET # 1630

Plugged through: TBG

District: 04

Signed  4/22/15 CKM
(TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 27 2015

APR 20 2015

CONSERVATION DIVISION
WICHITA, KS