

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-07094-00-00
Spot: SESWNE Sec/Twnshp/Rge: 26-14S-14W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: J BOXBERGER Well #: 4
County: RUSSELL Total Vertical Depth: 3023 feet

Operator License No.: 34912
Op Name: C12 KANSAS OIL, LLC
Address: 1900 WAZEE ST. SUITE 200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2917		100 SX
SURF	10	751		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2015 2:00 PM
Plug Co. License No.: 34946 Plug Co. Name: ACE WELL SERVICE, INC.
Proposal Rcvd. from: AVEN WEAVERLING Company: C-12 KANSAS OIL LLC Phone: (785) 623-3221

Proposed Plugging Method:	03/24/2015- Ordered 300 sx 60/40 pozmix 4% gel cement and 600 # hulls.
	03/25/2015- Ordered 300 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2015 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

03/24/2015- Drilled and cleaned out to 2990'. Pumped 300 sx cement w/600 # hulls. Pulled tubing.
03/25/2015- Tagged T.O.C. at 1235'. Perforated at 800' and 325'. Ran tubing to 1100' and pumped 180 sx cement w/150 # hulls. Cement circulated to the pit. Hooked to braden head and pumped 85 sx cement with little psi. Shut in on slight vacuum. Topped 7" casing off with 10 sx cement. Checked 10" after cutting off casing.
03/27/2015- 10" down 50-60'. Will top off.

GPS: 38.60650 -098.84220

Perfs:

Top	Bot	Thru	Comments
2917	3023		
2317	2321		
2313	2315		

Remarks: QUALITY CEMENTING TICKET # 1156

Plugged through: TBG

4/22/15 CKM

District: 04

Signed Ray Dinkel
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

APR 20 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MAR. 30 2015