

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21782-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 13-25S-32W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease Name: HICKS Well #: 3-13
County: FINNEY Total Vertical Depth: 2900 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2899	0	WITH 675 SX CMT
SURF	8.625	900		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/18/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 250# HULLS & 100 SX CMT. DISPLACE TO 1000'. TEST CASING TO 700#. RUN CBL FROM 1000' TO TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2015 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING FROM 2639' TO 0' USING 300# HULLS & 200 SX CMT. PRESSURED TO 500#. HOLDING. PUMP 15 SX CMT DOWN THE ANNULUS TO 250#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2569	2639		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed *Ken Jehlik* 4/22/15 CKM
(TECHNICIAN)

RECEIVED
APR - 6 2015 MSA
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION Form CP-2/3
APR 13 2015
CONSERVATION DIVISION
WICHITA, KS