

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-30095-00-01  
Spot: SWNE Sec/Twnshp/Rge: 13-21S-41W  
1980 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: BENGTSON Well #: 1-13  
County: HAMILTON Total Vertical Depth: 2793 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	2793	0	WITH 150 SX CMT
SURF	8.625	391		WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/09/2015 8:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/09/2015 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 50# HULLS AT 2677' THROUGH 1 1/2" TBG INSIDE OF 2 7/8" CASING. ESTIMATED TOP OF PLUG = 1700'. TOOH WITH 1 1/2" TBG. PRESSURE TEST 2 7/8" CASING TO 500#. HOLDING. PERFORATE AT 1240'. INJECTION RATE 1 BPM @ 600#. PUMP 55 SX CMT WITH 25# HULLS IN THE LAST 10 SX CMT AT 1 BPM @ 600#. NO CIRCULATION UP ANNULUS. DISPLACE CMT TO 700'. PERFORATE AT 440'. CIRCULATE CMT TO SURFACE WITH 80 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2786	2791		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
Received  
KANSAS CORPORATION (TECHNICIAN)

4/22/15 CKM

SA

RECEIVED  
APR 10 2015  
KCC DODGE CITY

APR 16 2015  
CONSERVATION DIVISION  
WICHITA, KS