

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-00779-00-00  
Spot: NW NESW Sec/Twnshp/Rge: 18-30S-8W  
2310 feet from S Section Line, 1650 feet from W Section Line  
Lease Name: MESSENGER B Well #: 1-18  
County: KINGMAN Total Vertical Depth: 4305 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4305	3030	150 SX
SURF	8.625	400		300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2015 12:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/13/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SET CIBP @ 4148' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 3030' PULLED CASING. TRIPPED TUBING INTO 1356' SPOTTED 35 SXS CLASS A CEMENT, WITH 3% CC. PULLED TUBING TO 909' SPOTTED 35 SX CLASS A CEMENT WITH 3% CC. PULLED TUBING TO 448' CIRCUALTED TO SURFACE WITH 160 SX CLASS A CEMENT.

Remarks: ALLIED CEMENT OUT OF MEDICINE LODGE PROVIDED CEMENT. TICKET #65023. DENIED TA.

Plugged through: TBG

4/22/15 CKM

District: 02

Signed BJ Hope

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 20 2015

CONSERVATION DIVISION  
WICHITA, KS

JK