

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-10014-00-00
Spot: NWNENW Sec/Twnshp/Rge: 18-30S-8W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MESSENGER B Well #: 3-18
County: KINGMAN Total Vertical Depth: 4334 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4334	3022	150 SX
SURF	8.625	407		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2015 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/07/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

SET CIBP @ 4220' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 3022' PULLED CASING. TRIPPED TUBING INTO 1348' SPOTTED 35 SXS CLASS A CEMENT, WITH 3% CC. PULLED TUBING TO 909' SPOTTED 35 SX CLASS A CEMENT WITH 3% CC. PULLED TUBING TO 440' CIRCUALTED TO SURFACE WITH 110 SX CLASS A CEMENT.

Remarks: ALLIED CEMENT OUT OF MEDINCE LODGE PROVIDED CEMENT. TICKET #MLK13032738. DENIED TA.

Plugged through: TBG

4/22/15 CKM

District: 02

Signed B. J. Hope

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

APR 20 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS