

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-30240-00-01
Spot: SESE Sec/Twnshp/Rge: 27-32S-10W
4659 feet from N Section Line, 683 feet from E Section Line
Lease Name: O' HARA Well #: 3
County: BARBER Total Vertical Depth: 4735 feet

Operator License No.: 33235
Op Name: CHIEFTAIN OIL CO., INC.
Address: 101 S. 5TH ST. PO BOX 124
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4308		WITH 2 SX CMT
PROD	5.5	4735	2500	WITH 125 SX CMT
SURF	8.625	219		WITH 175 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 04/15/2015 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4308' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2015 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4308' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 599' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 252' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4396	4406		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

Stephen Pfeifer
(TECHNICIAN)
SA

4/22/15 CKM

RECEIVED
APR 16 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION
Form CP-2/3
APR 20 2015
KANSAS CORPORATION COMMISSION
APR 20 2015
CONSERVATION DIVISION
WICHITA, KS
4-20-15