

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-091-22163-00-00  
Spot: SESENE Sec/Twnshp/Rge: 31-14S-22E  
4125 feet from S Section Line, 165 feet from E Section Line  
Lease Name: KNABE Well #: 11  
County: JOHNSON Total Vertical Depth: 946 feet

Operator License No.: 35170  
Op Name: DE & TZ LLC  
Address: PO BOX 128  
WELLSVILLE, KS 66092

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	945		108 SX
SURF	6.25	20		6 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2015 12:00 PM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: BRYAN MILLER Company: DE & TZ LLC Phone: (785) 883-4057

Proposed Plugging Method: Run 1" tubing to TD. Wash well through 1". Pump cement through 1" tubing and fill up well from bottom to top. Remove 1" tubing and top off well.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/16/2015 12:30 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

RAN 1" PIPE DOWN TO BOTTOM INSIDE THE PRODUCTION CASING AND PUMPED 10 SACKS OF CEMENT. PULLED THE 1" PIPE UP TO 700' AND PUMPED 10 SACKS OF CEMENT TO THE SURFACE. PULLED THE 1" PIPE OUT AND HOOKED ON TO THE CASING AND SQUEEZED AN ADDITIONAL 5 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
885	903		

RECEIVED  
KCC DIST # 3  
APR 16 2015  
CHANUTE, KS  
TH

Remarks:

Plugged through: TBG

District: 03

Signed Taylor Herman  
(TECHNICIAN)

4/22/15 CPM

Received  
KANSAS CORPORATION COMMISSION  
APR 20 2015  
CONSERVATION DIVISION  
WICHITA, KS  
Form CP-2/3