

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-23804-00-00
Spot: NESW Sec/Twnshp/Rge: 25-15S-14W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: J. SCHWEIN Well #: 1
County: RUSSELL Total Vertical Depth: 3400 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3393	1906	200 SX
SURF	8.625	468		210 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2015 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DAVID FUNK Company: JASON OIL CO. Phone: (785) 483-1071

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2015 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

03/25/2015- Sanded back to 2940' and topped with 5 sx cement.
03/26/2015- Cut casing at 1906'. Pulled casing to 1450' and pumped 125 sx cement w/300 # hulls. Pulled casing to 810' and pumped 40 sx cement w/100 # hulls. Pulled casing to 450' and pumped 120 sx cement. Cement circulated to the pit. POOH. Cellar stayed full.
Pulled 47 joints of 5 1/2" casing = to 1906'. 1,487' of 5 1/2" casing in hole.

GPS: 38.71671 -098.83126

Remarks: QUALITY CEMENTING TICKET # 1228

Plugged through: CSG

4/22/15 CKM

District: 04

Signed

Ray Dinkel

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

MAR 30 2015

APR 20 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS