

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-20420-00-00  
Spot: SWSESESE Sec/Twnshp/Rge: 31-23S-17E  
270 feet from S Section Line, 510 feet from E Section Line  
Lease Name: FRED ELLIS B Well #: 3  
County: WOODSON Total Vertical Depth: 925 feet

Operator License No.: 3728  
Op Name: KENT, ROGER DBA R J ENTERPRISES  
Address: 22082 NE NEOSHO RD  
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	925		100 SX
SURF	7	40		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/04/2015 12:00 AM  
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES  
Proposal Rcvd. from: JASON KENT Company: \_\_\_\_\_ Phone: (785) 448-4101

Proposed Plugging Method: Hook on well and fill well to surface

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 03/04/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the 2" casing to TD. Ran 1" pipe down the backside of the 2" casing inside the 7" casing to 150' hit cement. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled 1" pipe out of 2" casing. Pumped and circulated cement through the 1" pipe on the backside of the 2" casing inside the 7" casing from TD to surface. Pulled 1" pipe. Topped the well off with cement. A total of 60 sacks of portland cement was reported used to plug this well.

RECEIVED  
KCC DIST # 3  
APR 15 2015  
CHANUTE, KS

RD

4/22/15 CKM

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

APR 17 2015

CONSERVATION DIVISION  
WICHITA, KS