

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-20421-00-00
Spot: SENESESE Sec/Twnshp/Rge: 31-23S-17E
775 feet from S Section Line, 160 feet from E Section Line
Lease Name: FRED ELLIS B Well #: 4
County: WOODSON Total Vertical Depth: 927 feet

Operator License No.: 3728
Op Name: KENT, ROGER DBA R J ENTERPRISES
Address: 22082 NE NEOSHO RD
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	927		100 SX
SURF	7	40		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/04/2015 12:00 AM
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES
Proposal Rcvd. from: JASON KENT Company: _____ Phone: (785) 448-4101

Proposed Plugging Method: Hook on well and fill well to surface

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 03/06/2015 1:00 PM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing to TD. Ran 1" pipe down the backside of the 2" casing inside the 7" to 650' Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled the 1" pipe. Pumped and circulated cement through the 1" pipe outside the 2" casing and inside the 7" casing from 650' to surface. Pulled the 1" pipe. Topped the well off with cement. A total of 60 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
APR 15 2015
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

4/22/15 CCM

District: 03

Signed _____
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 17 2015

CONSERVATION DIVISION
Wichita, KS