

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-22234-00-00  
Spot: S2NWNE Sec/Twnshp/Rge: 25-26S-11W  
977 feet from N Section Line, 1983 feet from E Section Line  
Lease Name: ZINK "A" Well #: 1  
County: PRATT Total Vertical Depth: 4370 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3740		WITH 2 SX CMT
PROD	5.5	4373	1796	WITH 200 SX CMT
SURF	8.625	490		WITH 350 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/08/2015 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK 50' ABOVE PERFS & 5 SX CMT. PLUG AT 700' WITH 10 SX GEL & 40 SX CMT. PLUG AT 520' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER  
Date/Time Plugging Completed: 04/08/2015 11:40 AM

Witness Type: COMPLETE (100%)  
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3740' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 700' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 530' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4295	4298		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

4/22/15 CKM

District: 01

Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

RECEIVED  
APR 16 2015  
KCC DODGE CITY

5A

Received  
KANSAS CORPORATION COMMISSION  
Form CP-2/3  
APR 20 2015  
CONSERVATION DIVISION