

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-20285-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 21-21S-13W  
165 feet from N Section Line, 4620 feet from E Section Line  
Lease Name: SAMUEL Well #: 2  
County: STAFFORD Total Vertical Depth: 3703 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3700	1726	WITH 100 SX CMT
SURF	8.625	353		WITH 280 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/14/2015 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS & 4 SX CMT. PLUG AT 760' WITH 10 SX GEL & 50 SX CMT. PLUG AT 370' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/14/2015 6:15 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SANDED BACK TO 3600' WITH 5 SX CMT. 1ST PLUG AT 1720' WITH 50 SX CMT DUE TO OIL FLOWING TO SURFACE FROM GAS ZONE. 2ND PLUG AT 780' WITH 10 SX GEL & 50 SX CMT. 3RD PLUG AT 375' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3700	3703		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

4/22/15 CKM

District: 01

Signed Robert Dickerson

(TECHNICIAN)

RECEIVED  
APR 15 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 20 2015

CONSERVATION DIVISION  
WICHITA, KS