

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21567-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 23-20S-16W
4961 feet from S Section Line, 1991 feet from E Section Line
Lease Name: NELSON "A" Well #: 5
County: PAWNEE Total Vertical Depth: 3887 feet

Operator License No.: 30737
Op Name: M.A. YOST OPERATIONS, INC
Address: 30 N BROOKS PO BOX 811
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3881	2100	WITH 175 SX CMT
SURF	8.625	1073		WITH 465 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2015 7:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MACINTYER Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUG AT 3710' WITH 200# HULLS & 35 SX CMT. PLUG AT 1120' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2015 9:00 AM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

PUMP DOWN 2 3/8" TBG WITH 200# HULLS & 35 SX CMT. SHUT IN WITH 100 PSI. TAGGED TOC @ 3611'. 1ST PLUG AT 1116' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 419' WITH 40 SX CMT. 3RD PLUG AT 41' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3780	3786		
3770	3774		
3762	3766		
3760	3762		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

4/22/15 CKM

District: 01

Signed Robert Dickerson

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

RECEIVED
APR - 8 2015
KCC DODGE CITY

SA

APR 20 2015

CONSERVATION DIVISION
WICHITA, KS