

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name William Gruenerwald & Associates

Complete Address Box 909, Colorado Springs, Colorado 80901

Lease Name Woodworth Well No. 1

Location SW NE Sec. 6 Twp. 32 Rge. 31 (E) (W)

County Seward Total Depth 5975'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 1:00PM Day 30 Month 12 Year 1970

The above well was plugged as follows:

8 5/8" to 1638' circulated w/ cement. 2 7/8" to 5975' cemented.

Top perforations 4971' Plug bottom w/ 8 sacks cement.

Top of cement 4000' Mud 4000' to to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug. Halls 15 sacks cement 45' to 0'. Company Pump

Pulled 2800' of 2 7/8" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edward J. Eves
Well Plugging Supervisor

INVOICED
DATE 1-6-71
INV. NO. 3160-W