

P
~~CP-3~~

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-4-62
SEP 4 1962

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J.M. Huber Corp.

Complete Address: Box 978 Liberal, Kansas

Lease Name Reiss Well No. 1

Location C' NW: SE Sec. 29 Twp. 32S Rge. 31 (E) (W)

County Seward Total Depth 6000'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Daco Lease & Well Service

Address: Borger, Texas License No. 138

Operation Completed: Hour 11:30AM Day 31 Month 8 Year 62

The Above well was plugged as follows:

8 5/8" 2599' Circulated w/300 sax. cement.

4 1/2" 6000' Cemented. Perforations 5540' to 5548'

Cement 6000' to 5121'

Heavy mud 5121' to 700' Plug and 35 sax. cement 700' to 595'

Heavy mud 595' to 45' Plug and 15 sax. cement 45' to Surface.

Shot 4 1/2" at 1603' Weld cap on surface pipe.

(Halliburton Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/5/62

INV. NO. 5636-w

Signed: *Hugh Scott*
Well Plugging Supervisor