

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-175-20, 645-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name TUCKER PRODUCTION CORPORATION

Complete Address 2546 WEST MAIN, LITTLETON, COLORADO, 80120

Lease Name HUTCHINSON HOSPITAL FOUNDATION Well No. # 1-28

Location Q-NW-NE Sec. 28 Twp. 32 Rge. 31 (East)(West)

County SEWARD Total Depth 6010 FE

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor J. B. BOHANNAN (RIG. F) (REED WARNER)

Address _____ License No. _____

Operation Completed: Hour: 1:00 AM Day: 9th Month: JULY Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: 1/500st 6 1/2% Formix 6% GEL. 3% CA-CL.
8 5/8" - 1627^{FE} SD. CUC. 1/700st 1/200st CLASS H. 2% CA-CL.
ORDERED 175st 50% Formix 4% GEL. - 3% CA-CL. + 8 5/8" PLUG.
SPOTTED WITH DRILL STEM - WITH HEAVY SAND BETWEEN ALL PLUGS.

- 1st PLUG. @ 2950' 1/25st CMT.
- 2nd PLUG. @ 2660' 1/25st CMT.
- 3rd PLUG. @ 1680' 1/50st CMT.
- 4th PLUG. @ 720' 1/50st CMT.
- 5th PLUG. - SOLID BRIDGE PLUG @ 46^{FE} 1/10st CMT. - 10 IN RAT. HOLE - 5st HOUSE ABLE.

Amount of Surface Casing: 1627 FE CEMENTED BY HALLIBURTON.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

CLARENCE THOMAS JR. ON SICK LEAVE, I GAVE VERBAL PLUGGING INSTRUCTIONS.

Signed: [Signature]
Conservation Division Agent
RECEIVED
STATE CORPORATION COMMISSION

INVOICED
DATE 7-23-82
INV. NO. 738-W

JUL 20 1982

195,33