

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 3 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas 67901

Lease Name Richardson Well No. 1

Location SW SE Sec. 26 Twp. 32 Rge. 31 (E) (W)

County Seward Total Depth 5982'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:30PM Day 5 Month 1 Year 1968

The Above well was plugged as follows:

8 5/8" to 1572' circulated w/ cement. 4 1/2" to 5754' cemented.

Top perforations 5565' Plug bottom w/ 15 sacks cement

Top of cement 4900' Mud 4900' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 40'

Plug, Halls & 15 sacks cement 40' to 0' Company Pump.

Pulled 4423' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 5/3/68  
INV. NO. 9680-W