

15-179-20079-0000

KANSAS

Form CP-3

Rev 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 13 1978  
2-13-78  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Allied Materials Corp.

Complete Address Box 12300, Oklahoma City, Okla. 73112

Lease Name Angell "A" Well No. 1

Location C SE SE Sec. 24 Twp. 32 Rge. (E) (W) 31

County Seward Total Depth 5609' <sup>6020</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Sargent Casing Pulling

Address Liberal, Kansas License No. 511

Operation Completed: Hour 4 P Day 11 Month 2 Year 1978

The above well was plugged as follows:

Total Depth <sup>6020</sup> 5609' 8 5/8 csg set 1588' cwc

5 1/2 csg set 5609' cw 200 sk cmt. PFS (4900'-4910')

Pumped down 5 1/2 csg with lhull & 20 sk cem. Top of cement 4800'

Cutoff & recovered 2720' of 5 1/2 csg.

Filled hole with gel & water.

Set 35 sk cmt plug (700'-600')

Set 15 sk cmt plug 45' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. W. Massey  
Well Plugging Supervisor

DATE 2-14-78

INV. NO. 6758-6