

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Yucca Petroleum Company
Complete Address Box 2585, Amarillo, Texas 79105
Lease Name Krause Well No. 1
Location C SE SE Sec. 23 Twp. 32 Rge. 31 (E) (W)
County Seward Total Depth 6068'
Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Daco Lease & Well Service
Address Borger, Texas License No. 138
Operation Completed: Hour 5:00Pm Day 27 Month 2 Year 1974

The above well was plugged as follows:

8 5/8" to 1671' circulated w/ cement. 5 1/2" to 6067' cemented.
Top perforations 3080' Plug bottom w/ 25 sacks cement.
Top of cement 2950' Mud 2950' to 1000'
Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'
Plug, Hulls & 15 sacks cement 45' to 0' Daco Pump
Pulled 2222' of 5 1/2" casing.

INVOICED
I hereby certify that the above well was plugged as herein stated.
DATE 3/5/74
INV. NO. 8705-W

Signed: [Signature]
Well Plugging Supervisor