

15-175-10138-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*24*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Anadarko Production Company

Complete Address Box 351, Liberal, Kansas

Lease Name Singley Well No. 1

Location C NE SW Sec. 34 Twp. 32 Rge. 31 ~~(E)~~ <sup>(W)</sup>

County Seward Total Depth 6250'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 2:00PM Day 13 Month 3 Year 1970

The above well was plugged as follows:

8 5/8" to 2309' circulated w/ cement. 4 1/2" to 6083' cemented,

Top perforations 5515' Plug bottom w/ 20 sacks cement.

Top of cement 4800' Mud 4800' to 600'

Spotted 35 sacks cement 600' to 500' Mud 500' to 450'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump.

Pulled 3606' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar J. Egan*  
Well Plugging Supervisor

INVOICED  
DATE 3/17/70  
INV. NO. 1602-U