

15-175-10139-0000

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION
JAN 3 1963
CONSERVATION Division
Wichita, Kansas

Operator's Full Name Whitestone Petroleum Corp.

Complete Address: 900 Vaughn Bldg. Dallas, Texas

Lease Name Barnum Well No. # 1

Location NW/4 Sec. 30 Twp. 32S Rge. (E) (W) 31

County Seward Total Depth 6046'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling Service

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 5 PM Day 30 Month 12 Year 62

The Above well was plugged as follows:

13 3/8" 560' Circulated w/cement. 8 5/8" 2291' Circulated w/cement.

4 1/2" 5651' Cemented. Plug Back To. -5618' Top Perforations. -5556'

Sand hole 5618' to 5530' 5 sax.cement 5530' to 5465'

Mud 5465' to 700' Plug and 35 sax.cement 700' to 600'

Mud 600' to 50' Rock Bridge 50' to 40'

15 sax.cement 40' to Surface. Weld cap on surface.

Pulled 2578' 4 1/2" Piped. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]

Well Plugging Supervisor

DATE

INV. NO.

1/4/63
6250-4