

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM.
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 28 1964

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Kuhn of Walter Kuhn Drilling Co. has this
 date requested permission to plug the following described well:

Mr. Kuhn guarantees payment of the plugging fee.

Operator's full Name: Walter Kuhn Drilling Co.

Complete Address: 726 Union Center Bldg. Wichita, Kansas

Lease Name: Prater Well No. # 1

Location: C SW Sec. 29 Twp. 32S Rge. (E) (W) 32

County Seward Total Depth 2736' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Kuhn was instructed to plug the well as follows:

8 5/8"-565' Circulated w/cement. 5 1/2"-2734' Cemented.

Top perforations 2720' Plug back to 2734' W/cement.

Plug bottom w/35 Sax.cement top cement 2450' Mud 2450' to 565'

35 Sax.cement 565' to 465' Mud 465' to 45'

15 Sax.cement 45' to 0

Very truly yours,

Conservation Division Agent