

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gatlin of Anadarko Production has this
date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Binney "A" Well No. 1

Location: NE NE SW Sec. 25 Twp. 32 Rge. 32 XX (E) (W)

County: Seward Total Depth 6160' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 1633' circulated w/ cement. Mud 6160' to 1600'

Spot 40 sacks cement 1600' to 1460' Mud 1460' to 450'

Plug, Hulls 20 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent