

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
OCT 23 1967
10-23-67
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Whaley of Getty Oil Co. has this

date requested permission to plug the following described well:

Mr. Whaley guarantees payment of the plugging fee.

Operator's full Name: Getty Oil Company

Complete Address: Box 752, Drumright, Oklahoma

Lease Name: F.E. Dufield Well No. 1

Location: App C SW NE Sec. 14 Twp. 32 Rge. 32 (E) (W)

County Seward Total Depth 7280' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Whaley was instructed to plug the well as follows:

8 5/8" to 2203' circulated w/ cement. 4 1/2" to 6200' cement ed

Top perforations 2726' Plug bottom w/ 20 sacks cement

Top of cement 2480' Mud 2480' to 600'

Spotted 40 sacks cement 600' to 500' Mud 500' to 35'

Plug, Halls & 10 sacks cement 35' to 0'

Very truly yours,

Edmund J. Evers
Conservation Division Agent