

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1963  
10-31-63

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Red Bishop of Leben Drilling Inc. has this date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Inc.

Complete Address: 905 Central Bldg., Wichita, Kansas

Lease Name: Kostner Well No. # 1

Location: C SW SW Sec. 6 Twp. 29 Rge. 5 (E) (W) W

County Kingman Total Depth 4400 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Bishop was instructed to plug the well as follows:

194' of 8. 5/8" surface pipe, cemented with 100 sacks.  
Fill hole with drilling mud to 240', 1st cementing plug,  
1/2 sack hulls, cement with 30 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, 1/2 sack hulls, cement  
with 10 sacks to base cellar. Bridge and cement rat hole  
with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent