

2 100234

6-19-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
205 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 191-21,819-0000

SE NW NE, SEC. 22, T 30 S, R 1 W X E X

TECHNICIAN'S PLUGGING REPORT

Operator License # 4867

Operator: K.T. Allam Oil Operations

Name & Address 1603 Stoney Point

Wichita, KS 67212

(316) 721-3555

feet from S section line

feet from E section line

Lease Name Kelly Well # 1

County Sumner 127.37

Well Total Depth 3919 feet

Conductor Pipe: Size 5 1/2" feet 3886 100 sx

Surface Casing: Size 8 5/8" feet 418 100 sx

Abandoned Oil Well Gas Well Input Well SWD Well x D&A

Other well as hereinafter indicated Open hole from 3886 to 3919

Plugging Contractor Dewey Gressel License Number 5822

Address Haysville, KS 67060

Company to plug at: Hour: 10:00 Day: 19 Month: 6 Year: 19 87

Plugging proposal received from Curtis

(company name) Gressel Corporation (phone) 773-1247

were: Sand back to 3835, spot 6 sxs cement. Rip and pull pipe at 3000', mud to 450'

build bridge and redi mix to surface

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12:30 Day: 19 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3830' and dump with bailer 6 sxs of cement. Shoot

and pull pipe, 2563' of 5 1/2", bail hole and build bridge at 525'. Fill with 6 1/4

yards redi mix to surface.

RECEIVED
STATE CORPORATION COMMISSION

JUN 25 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Wellington Redimix #56839

(if additional description is necessary, use BACK of this form.)

INVOICED (add note) observe this plugging.

DATE 6-25-87

INV. NO. 17346

Signed J.C. Sanders
(TECHNICIAN)