

2 050365

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 191-21,800-0000

NE SW NE, SEC. 22, T 30 S, R 1 ~~W~~

3630 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9755

Lease Name Nixon Well # 1

Operator: Advanced Recovery

County Sumner 127.24

Name & Address P.O. Box 5351

Well Total Depth 3915 feet

Englewood, CO 8051

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor M & B License Number

Address Wellington, KS

Company to plug at: Hour: Day: Month: 3 Year: 19 86

Plugging proposal received from

(company name) (phone)

were: 5 1/2" set at 3910 feet - sand to 3850 feet and dump 6 sacks of cement -
shoot and pull pipe - squeezed 8 5/8" with 15 sacks of gel, 3 sacks of hulls, 130
sacks of cement

Plugging Proposal Received by Glenn Ward
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 p.m. Day: 28 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT Sanded back to 3850 feet and dumped 6 sacks of cement. Shot and
pulled 2510 feet of 5 1/2" casing. Squeezed 8 5/8" with 15 sacks gel, 3 sacks of hulls
and 175 sacks 60/40 pos mix cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 11 1986 4-11-86

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Howco #355674
(If additional description is necessary, use BACK of this form.)

INVOLVED

observe this plugging.

DATE APR 11 1986

Signed Glenn Ward
(TECHNICIAN)

INV. NO. 13376

3-28