

44

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name J.M. Huber Corp.

Complete Address: Box 978 Liberal, Kansas

Lease Name Neff Well No. # 1

Location C SW NE Sec. 2 Twp. 35 S Rge. 32 (E) (W)

County Seward Total Depth 6270'

Abandoned Oil Well X Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Daco Lease & Well Service

Address: Borger, Texas License No. # 138

Operation Completed: Hour 2 PM Day 25 Month 10 Year 62

The Above well was plugged as follows:

13 3/8" 400' Cir.w/cement. 9 5/8" 2400' Cir.w/cement. 7" 6014' Cem.

Plug back to 6014' Perf. 5965' to 5975'

Plug bottom w/50 sax.cement 5700' to 6014'

Mud 5700' to 750' Plug and 35 sax.cement 750' to 665'

Mud 665' to 35' Plug and 15 sax.cement 35' to surface.

Well cap on pipe. Pulled 2611' 7".

(Halliburton Cementing Co.)

I hereby certify that the above well was plugged as herein stated.
Signed: [Signature]
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
10-26-62
OCT 26 1962

DATE 10/29/62

INV. NO. 59.15-W

CONSERVATION DIVISION
Wichita, Kansas