

15-175-10182-0000

Form CP-3
Rev. 6-4-68

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name J.M. HUber Corporation

Complete Address Box 911, Amarillo, Texas

Lease Name Neff Well No. 2

Location NW NE Sec. 2 Twp. 35 Rge. 32 ~~(E)~~ (W)

County Seward Total Depth 6108'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated None

Plugging Contractor Daco Lease & Well Service

Address Borger, Texas License No. 138

Operation Completed: Hour 2:00PM Day 28 Month 8 Year 1970

The above well was plugged as follows:

13 3/8" to 400' circulated w/ cement.	9 5/8" to 2400' circulated w/ cement.
7" to 6145' cemented	Top perforations 5932'
Plug bottom w/ 60 sacks cement	Top of cement 5848'
Mud 5848' to 900'	Spotted 40 sacks cement 900' to 800'
Mud 800' to 45'	Plug, Hulls & 15 sacks cement 45' to 0'.
Company Pump	Pulled 2613' of 7" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 9/1/70
INV. NO. 2463-W