

RECEIVED
STATE CORPORATION COMMISSION
11-9-81
NOV 9 1981
FORM CP-3
CONSERVATION DIVISION
Wichita Kansas

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

Authority Oct 21, 1981
API Number 15-

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Amoco Production Company

Complete Address PO Box 437, Liberal Kansas 67901

Lease Name Feather Gas Unit Well-No. 1

Location C. Sw. Sw. Sw. Sec. 15 Twp. 35 Rge. 33 (East)(West)

County Seward Total Depth 8243

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling

Address Sublette Kans. License No. 766

Operation Completed: Hour: 1:30 PM Day: 6 Month: Oct Year: 1981

Plugging Operations attended by Agent?: All Part X None

The above well was plugged as follows:

There was 651' of 13 3/8 surface casing c.c.
There was 2487' of 9 5/8 surface casing
5 1/2" was set to 6152'. Well was open hole
set cast iron bridge plug at 6125. with
2 shs cement on top. Shot pipe at 2745'. Put
45 shs plug at 2715-2615. Put bridge plug at
2410' with 2 shs cement. Shot 9 5/8. 902'. Put 90
shs at 870-770. Put 120 sh. at 700-600. 50 sh. at 50-0
Salvage. 2745' of 5 1/2" - 902' of 9 5/8 casing.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Flarence Thomas
Conservation Division Agent

INVOICED

DATE 11-17-81
8290-W