

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-175-20,630

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name LADD & LUKOWITZ

Complete Address 1600 BROADWAY #1730 DENVER, COLORADO 80202

Lease Name MING Well No. # 1-8

Location C-1/2-SUN Sec. 8 Twp. 35 Rge. 33 (East)(West)

County SEWARD Total Depth 6685 FE

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor RAMAC DRILLING (RIG 3) TED BROWN.

Address P.O. BOX 1164 GREAT BEND, MO. License No. _____

Operation Completed: Hour: 12:30 AM Day: 6th Month: MAY Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 1515 FE SR CUL #/800ST HALLIBURTON LIGHT + CLASS H. #/2% CA-CL
ORDERED 200ST 50/50 FORMIX 4% GEL. 3% CA-CL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST Plug @ 3000 FE #/25ST CMT.

2ND Plug @ 2560 FE #/35ST CMT.

3RD Plug @ 1500 FE #/60ST CMT.

4TH Plug @ 330 FE #/50ST CMT.

5TH Plug. 50110 BRIDGE HANDS + PLUG @ 46 FE #/10ST CMT. 7 10ST IN RAT HOLE (CIRCUMFER)

Amount of Surface Casing: 1515 FE

10ST IN MOUSE HOLE (CEMENTED BY HALLIBURTON)

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Martin Schmidt
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I GAVE VERBAL PLUGGING ORDERS FOR SUPERVISOR CLARENCE THOMAS.
SINCE HE IS ON SICK LEAVE.

Signed: Martin Schmidt
Conservation Division Agent

INVOICED

DATE 5-24-82

INV. NO. 250-W

RECEIVED
STATE CORPORATION COMMISSION
5-10-82
MAY 10 1982
CONSERVATION DIVISION
Wichita Kansas