

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_  
LOCATION Center SE $\frac{1}{4}$   
SEC. 18 TWP. 34 RGE. 38W

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease Osmon  
Operator Alf Landon & Kuhn Address Topeka, Kansas  
Field Hugoton County Stevens  
Total Depth 2854 Feet.

(Describe briefly the manner in which the well was plugged)

Water broke in at approximately 1300 feet the after noon of March 3, 1951. Well was left open, blowing lots of slightly salty water and red sand until rig was moved in. Halliburton set plug below bad place in pipe and squeezed with 400 sacks of cement, something went wrong with the cementing plug, leaving cement in the casing to within 300 feet of the top. Then cement was drilled out to a few feet the bad place in the pipe. At this place the tools began sticking, the tools were <sup>below</sup> pulled out, they ran swedge with long stroke jars which stuck in the pipe after jarring for sometime trying to get loose, the tools were pulled out leaving the swedge and long stroke jars in the hole.

April 5 1951 Halliburton ran 200 sacks of cement in hole and that evening about 7:00 I noticed they had welded a steel cap on top of casing.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 18 1951 618-51

CONSERVATION DIVISION  
Wichita, Kansas  
R. J. Phillips  
District Conservation Agent

Date April 5 1951

PLUGGING  
FILE SEC 18 T 34 R 38W  
BOOK PAGE 85 LINE 29