

R

DISTRICT CONSERVATION AGENT'S REPORT

To

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

File No. 113-30

Location S E - N W

Sec. 16 Twp. 34 Rge. 38

I have today completed supervision of plugging of:

Well No. 1 Lease Kelley

Operator Panhandle Eastern P L Co Address 1221 Baltimore Ave. Kansas City, Mo.

Field Hugoton County Stevens

Total Depth 2815 Feet.

(Describe briefly the manner in which the well was plugged)

Well was plugged back to 2687' w/75 sacks of cement in September 1943.

Run 77 sacks of cement which plugged back to 2651', this cementing was completed August 1, 1945.

Plugged back to 2603' w/ rock & six sacks of cement August 2, 1945.

Put in bridge at 2180', filled up to 2170' with rock & mud and run 2 sacks of cement.

10' of rock & 4 sacks of cement after cement set filled hole, mud to ground Elev.

Took 6' of 5 3/16 out and capped with five sacks of cement

Pipe 5 3/16" was cemented w/30 sacks when pipe was run on April 27, 43 run 75 sack of Cement through split joint on May 6, 43 shot pipe at 1950 & cemented with 350 sacks.

District Conservation Agent

*R. J. Phillippe*

Date Aug 9-1945

**PLUGGING**  
FILE 16-34-38W  
BOOK PAGE 43 IS 30

