

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 10 1967  
3-10-67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name E. C. Mingenback O/A Well No. 1

Location App. Cented Sec. 31 Twp. 34 Rge. 39 (N) (W)

County Morton Total Depth 2815'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 6:30Pm Day 8 Month 3 Year 1967

The Above well was plugged as follows:

8 5/8" to 515' circulated w/ cement. 5 1/2" to 2814' ciru. w/ cement.

3 1/2" to 1510' w/ Packer Top perforations 2644'

Plug bottom w/ sand & 30 sacks cement. Top of cement 1360'

Mud 1360' to 500' Spotted 25 sacks cement 500' to 325'

Mud 325' to 75' Plug, Hulls & 10 sacks cement 75' to 0'.

Pulled 1510' of 3 1/2" casing & packer. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edmund J. Evers  
Well Plugging Supervisor

DATE 3/10/67  
INV. NO. 4889-W