

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 93-12

LOCATION C NE

SEC. 14 TWP. 34 RGE. 39W

Dry Hole            Abandoned Oil Well            Abandoned Gas Well Yes

I have today completed supervision of plugging of:

Well No. 1 Lease YOUNG

Operator KUHN BROTHERS Address 403 Union National Bank Bldg.,  
Wichita, Kansas

Field HUGOTON County STEVENS

Total Depth 2732 Feet. Elevation 3294

(Describe briefly the manner in which the well was plugged)

This well was completed April 1, 1936. 10 inch surface pipe was set at 620 feet. 7 inch OD casing set at 2551 feet cemented with 100 sacks of cement. First gas 2673 feet and more gas from 2695 to 2732 feet. 5 inch liner cemented at 2692, top of liner 2433 feet and 6 inches. On February 6, 1947, 100 sacks of cement pumped to bottom by Halliburton and 2000 gallons of water on top of cement. This cement filled up to 2570 feet and set hard. On Feb. 12, 1947, three truck loads of mud were put in hole on top of cement.

R. G. Philippe  
District Conservation Agent

Date February 12, 1947

FEB 24 1947  
2-24-47

14 34 39W  
93 12