

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name The Stevens County Oil & Gas Company Wichita, Kansas

Complete Address 301 American Savings Bldg. Wichita, Kansas

Lease Name Jenkins Well No. 1

Location C SW Sec. 10 Twp. 34 Rge. 39 (E) (W)

County Stevens Total Depth Approx 2700'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 11:00AM Day 25 Month 4 Year 1970

The above well was plugged as follows:  
13 3/8" to approx 675' circulated w/ cement. 8 5/8" to 2580' cemented.  
Open hole 2580' to T.D. Plug bottom w/ 85 sacks cement.  
Top of cement 2395' Mud 2395' to 500'  
Spotted 65 sacks cement 500' to 400' Mud 400' to 25'  
Plug. Hulls & 15 sacks cement 25' to 0'. Company Pump  
Pulled 1215' of 8 5/8" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward J. Green  
Well Plugging Supervisor

DATE 4/28/70  
INV. NO. 1802-W