

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 87-40LOCATION CSESEC. 9 TWP. 34 SRGE. 39WDry Hole Abandoned Oil Well Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease Snare Operator Sidwell et al Address 202 W.K.H. Bldg., Wichita, KansasField Hugoton County MortonTotal Depth 2790 Feet.

(Describe briefly the manner in which the well was plugged)

Halliburton pumped a plug to the top of the 5 $\frac{1}{2}$ " liner at 2620'. Put in 37' of rock and calseal. Ran 5 $\frac{1}{2}$ " string of casing. The casing stopped at 2526' and was unable to get the 5 $\frac{1}{2}$ " any lower so cemented it there with 150 sacks of cement. Plug circulated on the 5 $\frac{1}{2}$ " before cementing and it circulated with water. After cement was in, either the bridge gave away or the 7" casing burst below 2526' allowing all the cement to go to the bottom of the hole cementing it completely solid. Halliburton ran temperature survey which showed the cement to be behind the 5 $\frac{1}{2}$ " string of casing to 1760'. McCullough Tool Company shot the 5 $\frac{1}{2}$ " off at 1710'. Pumped the hole full of mud. Did not pull any 7" casing or surface pipe. Welded top of 10" surface casing after it was completely full of mud.

R.J. Phillippe
 District Conservation Agent

Date April 20, 1953

PLUGGING
 FILE SEC 9 T 34 R 39W
 BOOK PAGE 82 LINE 40