

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CORPORATION COMMISSION
MAR 8 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Cities Service Oil Company

Complete Address: Box 1028, Guymon, Oklahoma

Lease Name Cyr " B" Well No. 1

Location C SE SW Sec. 32 Twp. 34 Rge. 41 (E) (W)

County Morton Total Depth 5116'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Holm Drilling Co.

Address: Tulsa, Oklahoma License No.

Operation Completed: Hour 2:00AM Day 6 Month 3 Year 1967

The Above well was plugged as follows:

8 5/8" to 1446' ciru. w/ cement. Spotted 25 sacks cement 5100' to 5025'

Mud 5025' to 4840' Spotted 25 sacks cement 4840' to 4765'

Mud 4765' to 3305' Spotted 25 sacks cement 3305' to 3230'

Mud 3230' to 3100' Spotted 25 sacks cement 3100' to 3025'

Mud 3025' to 700' Spotted 35 sacks cement 700' to 600'

Mud 600' to 45' Plug. Hulls & 15 sacks cement 45' to 0'.

Haliburton Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edmund Eves
Well Plugging Supervisor

DATE 3/8/67

INV. NO. 4883-W