

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

*Called
11:00 AM -
Jan 4, 1975.*

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

*Intention to Drill issued
Nov 11, 1974 - 15-175-20, 244-0000*

RECEIVED
STATE CORPORATION COMMISSION
1-6-75
JAN 6 1975

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bill McKeen of Dodson Drilling has this date requested permission to plug the following described well:

Mr. McKeen guarantees payment of the plugging fee.

Operator's full Name: Trust Nat'l Oil Inc.

Complete Address: 23. E 11th, Liberal, Kans

Lease Name: Trisler Well No. #1

Location: SE. N.E. Sec 23 Twp. 32 Rge. (E)(W) 31

County: Seward Total Depth 3205 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. McKeen was instructed to plug the well as follows:

*There was 600 ft of 8 5/8 surface casing
set with 350 sacks of cement. Circulated
set 1st Plug of 60 sacks cement at 900ft
fill with heavy mud. 2nd Plug at 500ft
With 35 sacks of cement. Fill with heavy
mud. 3rd Plug at
45-0 ft with 15 sacks
of cement. 2 sacks in
rat hole*

Very truly yours,

Clarence L. Thomas
Conservation Division Agent