

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Martin of Trumart has this
date requested permission to plug the following described well:

Mr. Martin guarantees payment of the plugging fee.

Operator's full Name: Trumart Oil Comapny

Complete Address: Box 12, Ellis, Kansas

Lease Name: Holmes Estate Well No. 1

Location: NE SW SW Sec. 28 Twp. 32 Rge. 30 ~~(E)~~ (W)

County: Meade Total Depth 5682' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Martin was instructed to plug the well as follows:

13 3/8" to 505' circulated w/ cement. 9 5/8" to 2585' cemented.

.5 1/2" to 5676' cemented. Top perforations 5540'

Plug bottom w/ 20 sacks cement. Top of cement 5400'

Mud 5400' to 600' Spot 50 sacks cement 600' to 500'

Mud 500' to 40' Plug, Halls & 20 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent