

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 12 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of McAdams has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: McAdams Pipe & Supply

Complete Address: Box 960, Bristow, Oklahoma

Lease Name: Holmes Well No. 9

Location: C SE SW Sec. 35 Twp. 32 Rge. 30 XX  
(E)(W)

County: Meade Total Depth 5810' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1622' circulated w/ cement. 5 1/2" to 5797' cemented.


Top perforations 5713' Plug bottom w/ 40 sacks cement.

Top of cement 5500' Mud 5500' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent