

15-119-10020-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of McAdams has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: McAdams Pipe & Supply

Complete Address: Box 960, Bristow, Oklahoma

Lease Name: Holmes Well No. 8

Location: C SW SE Sec. 35 Twp. 32 Rge. 30 XX (E) (W)

County: Meade Total Depth 5886' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1614' circulated w/ cement. 5 1/2" casing to 5875' cemented.

Top perforations 5652' Plug bottom w/ 20 sacks cement.

Top of cement 5500' Mud 5500' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls ' 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent