

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Graham-Michaelis Drlg. Co has this  
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Drilling Company

Complete Address: 211 N. Broadway, Wichita, Kansas

Lease Name: Jones "B" Well No. 1

Location: C SE SE Sec. 34 Twp. 32 Rge. 30 (E) (W)

County Meade Total Depth 5820' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1545' circulated w/ cement. 5 1/2" to 5819' cemented.

Top Perf. 5702' Plug bottom w/ 20 sacks cement.

Top of cement 5600' Mud 5600' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Weld Plate on 8 5/8".

Very truly yours,

Edgar J. Eves  
Conservation Division Agent